



Bid Addendum #1
C-Dock Restroom Improvement Project
Port of Redwood City
May 24, 2018

1. Sheet 3.00 – Add to Fixture Schedule Item “B”
 - A. Delta Mixing Valve – R10000-IP
 - B. Delta Faucet Trim - D13091
 - C. Delta ADA Grab Bar and Handheld Shower – 52003-DS
 - D. Delta Elbow - 50560
2. Section 00400 Bid Forms and Supplements Item #14 – replace “water resistant drywall” with “cement backerboard”. Revised Proposal Form is attached.
3. Section 00400 Bid Forms and Supplements – Delete Item #21, Install shower stall wall. All work is covered in Item #14, Install 24 gauge steel stud wall Revised Proposal Form is attached.
4. Section 00400 Bid Forms and Supplements – Delete Item #22, Locate shower controls. All work is covered in Item #28, Install ADA shower and hook strip. Revised Proposal Form is attached.
5. Add electrical work to the project as follows:
 - A. Relocate 2 existing shower light switches at walls to be demolished to new walls at approximately the same location. Provide new boxes, wiring, switches, etc. as required.
 - B. Replace 4 existing GFCI receptacles with new GFCI receptacles (2 each in the Men’s Restroom and 2 each in the Women’s Restroom).
6. Section 00400 Bid Forms and Supplements – Add new Item #34 Electrical Work with Lump Sum amount for electrical work described in #5 above. Revised Proposal Form is attached.



PORT OF REDWOOD CITY
Serving Silicon Valley

675 Seaport Boulevard
Redwood City, California 94063-5568
650 306 4150 FAX 650 369 7636
E-mail: portofrc@redwoodcityport.com

Bid Addendum #1
C-Dock Restroom Improvement Project
Port of Redwood City
May 24, 2018

7. Section 01200 Price & Payment Procedures - Add new Item #34 Electrical Work stating the following: "Measurement and payment for this item shall be on a lump sum basis. The Contract lump sum price for this item shall include full compensation for providing all labor, tools, equipment and materials to install the electrical work described above and as directed by the Engineer and no additional compensation will be allowed therefore.
8. Sheet 1.00, Scope of Work #5 - Dur-A-Chip System by Dur-A-Flex is an acceptable alternate to the specified Dex-O-Tex product.
9. Bids shall be sealed and filed with the Port Executive Director at the Offices of the Port of Redwood City, California, on or before June 1, 2018 at 10:00 AM, and will be opened and publicly read aloud shortly thereafter of that day in the Office of the Port Executive Director, at 675 Seaport Blvd. Redwood City, California.

Item No.	EST. Qty.	Unit	Description of Item	Unit Price	Item Cost
1	1	LS	Mobilization (not to exceed 5% of total bid)		
2	1	LS	Demolition and removal of the items inside the bathroom, including cap and seal		
3	1	LS	Demolition and removal of the items outside the bathroom		
4	1	LS	Apply epoxy finish		
5	1	LS	Perform painting		
6	1	LS	Attach new walkway to edge of existing concrete slab, and new shower pan slab to existing slab		
7	1	LS	Install new tiles on walls		
8	1	LS	Install wire mesh between top of walls and ceiling		
9	8	LF	Construct 6" step		
10	35	LF	Construct 6" high x 6" wide concrete curb		
11	10	LF	Install 3" PVC sleeve under flatwork for future irrigation line		
12	93	SF	Construct 4" concrete walkway		
13	50	SF	Construct 4" concrete ramp		
14	150	SF	Install 24 gauge steel stud wall, 7'-6" high with 5/8" cement backerboard both sides. Provide backing as required for all wall mounted fixtures.		
15	3	EA	Install toilet partitions with 36" wide door		
16	8	EA	Install grab bar		
17	1	EA	Install laminate folding counter (33" high x 28" deep x 72" wide)		
18	2	EA	Install fixed counter (33" high x 18" deep x 40" wide)		

Item No.	EST. Qty.	Unit	Description of Item	Unit Price	Item Cost
19	3	EA	Install toilet paper and seat cover dispensers		
20	2	EA	Install shower curtain rod, hook and curtain		
21				XXX	XXX
22				XXX	XXX
23	2	EA	Install fold down shower seat		
24	2	EA	Install mirror and soap dispenser		
25	2	EA	Install 84" x 36" steel door with welded steel frame		
26	1	EA	Relocate (E) plumbing and dryer vent for new washer/dryer location		
27	3	EA	Install water closet		
28	2	EA	Install ADA shower and hook strip		
29	2	EA	Install lavatory		
30	2	EA	Install urinal		
31	2	EA	Mount paper towel dispenser		
32	2	EA	Install door and room signage		
33	1	EA	Relocate tight to the wall existing waterline to exterior hose bib		
34	1	LS	Electrical Work		

TOTAL BID AMOUNT IN NUMBERS

\$ _____

TOTAL BID AMOUNT IN WORDS: _____